

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-26221-00-00  
Spot: S2S2NWNE Sec/Twnshp/Rge: 15-13S-20W  
1300 feet from N Section Line, 1980 feet from E Section Line  
Lease Name: WEGELE Well #: 2  
County: ELLIS Total Vertical Depth: 3910 feet

Operator License No.: 33786  
Op Name: DOUBLE D'S LLC  
Address: 133 E 12TH  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/28/2011 12:00 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: DOUBLE D'S LLC Phone: (785) 628-1285

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS Witness Type: NONE  
Date/Time Plugging Completed: 11/28/2011 4:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:


1st. Plug at 3800' w/25 sxs.  
2nd. Plug at 1525' w/25 sxs.  
3rd. Plug at 720' w/100 sxs.  
4th. Plug at 272' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

CM

RECEIVED  
FORM CP 2/3

DEC 17 2011

KCC WIC.

DEC 08 2011