

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26179-00-00
Spot: NESWNENE Sec/Twnshp/Rge: 12-14S-19W
775 feet from N Section Line, 950 feet from E Section Line
Lease Name: PFANNENSTIEL Well #: 1-12
County: ELLIS Total Vertical Depth: 3894 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/07/2011 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DOWNING-NELSON OIL CO INC Phone: (785) 621-2610

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB Witness Type: NONE
Date/Time Plugging Completed: 12/07/2011 7:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:


1st. Plug at 3850' w/25 sxs.
2nd. Plug at 1441' w/25 sxs.
3rd. Plug at 700' w/100 sxs.
4th. Plug at 272' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____



(TECHNICIAN)

CM

DEC 08 2011

RECEIVED Form CP-2/3

DEC 12 2011

KCC WICHITA

12/14/11
A