

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22057-00-00

Spot: NESENE

Sec/Twnshp/Rge: 2-19S-30W

1623 feet from N Section Line,

333 feet from E Section Line

Lease Name: EHMKE

Well #: 1

County: LANE

Total Vertical Depth: 4672 feet

Operator License No.: 6569

Op Name: CARMEN SCHMITT, INC.

Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	220		WITH 170 SX CMT

PC		2226		WITH 175 SX CMT
----	--	------	--	-----------------

PROD	5.5	4652	0	WITH 200 SX CMT
------	-----	------	---	-----------------

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/22/2011 9:30 AM

Plug Co. License No.: 99981

Plug Co. Name: COPELAND ACID & CEMENT, INC.

Proposal Rcvd. from: FRANCIS HITSCHMANN

Company: CARMEN SCHMITT

Phone: (620) 793-5100

Proposed Plugging Method: PUMP 35 SX CMT & 200# HULLS, GEL SPACER TO 2250' THEN 25 SX CMT, GEL SPACER TO 1300'. CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/22/2011 10:30 AM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 35 SX CMT & 200# HULLS, 15 SX GEL & 25 SX CMT, 10 SX GEL & 150 SX CMT. PRESSURED TO 500# & HELD. PUMPED 5 SX CMT DOWN BACKSIDE & PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4411	4415		MARMATON
4317	4320		KC - LANSING

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

RECEIVED
DEC 12 2011
KCC WICHITA

District: 01

Signed

Michael J. Maier
(TECHNICIAN)

RECEIVED

NOV 30 2011

KCC DODGE CITY

Form CP-2/3

12/14/11