

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21601-00-00
Spot: SWSENE Sec/Twnshp/Rge: 6-25S-20W
2305 feet from N Section Line, 899 feet from E Section Line
Lease Name: BUTLER A Well #: 1-6
County: EDWARDS Total Vertical Depth: 4831 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	310		WITH 300 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/10/2011 1:30 PM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: SHANE DOWNS Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 1020' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 330' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 12/10/2011 3:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

Perfs:

1ST PLUG AT 1020' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 330' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY BASIC ENERGY

Plugged through: DP

District: 01

RECEIVED

DEC 12 2011

KCC DODGE CITY

Signed

Steve Durrant

(TECHNICIAN)

RECEIVED

DEC 13 2011

KCC WICHITA

Form CP-2/3

12/14/11