

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-19050-00-00
Spot: SENWNWSW Sec/Twnshp/Rge: 7-20S-21W
2103 feet from S Section Line, 580 feet from W Section Line
Lease Name: O BRIEN B Well #: 1
County: NESS Total Vertical Depth: 4365 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1100		
CIBP		4350		
SURF	8.625	508		WITH 250 SX CMT
PROD	4.5	4366	0	WITH 100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/18/2011 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: BENNIE DILLS Company: RITCHIE EXPLORATION Phone: (620) 793-2525

Proposed Plugging Method: RUN TBG TO BOTTOM & PUMP 70 SX CMT & 200# HULLS. SET CIBP @ 1100' & PRESSURE CASING TO 500# IF HOLDS PERFORATE AT 700' & PUMP 80 SX CMT OVER CASING VOLUME. TIE ONTO BACKSIDE & PUMP 150 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 11/18/2011 2:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4400' & PUMP 70 SX CMT & 200# HULLS. SET CIBP @ 1100' & PRESSURED CASING TO 500# & HELD. PERFORATED AT 700' & PUMP 125 SX CMT. DID NOT CIRCULATE. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD. PULLED SWEDGE & TOPPED OFF WITH 20 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4337	4344		MISSISSIPPI

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED OIL WELL.

Plugged through: TBG

RECEIVED
DEC 12 2011
KCC WICHITA

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
NOV 30 2011
KCC DODGE CITY

Form CP-2/3
12/16/11