

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22862-00-00
Spot: SENWSW Sec/Twnshp/Rge: 34-24S-15W
1591 feet from S Section Line, 4307 feet from E Section Line
Lease Name: STOVER Well #: 3A
County: STAFFORD Total Vertical Depth: 4500 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	333		WITH 225 SX CMT
PROD	5.5	4497	2160	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/10/2011 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: LD DRILLING Phone: (620) 793-3051

Proposed Plugging Method: SAND TO 4150' WITH 5 SX CMT. PLUG AT 1000' WITH 12 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/10/2011 4:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 4150' WITH 5 SX CMT. CUT CASING AT 2160'. PULLED ONE JOINT & WELL STARTED FLOWING. 1ST PLUG AT 2120' WITH 35 SX CMT. 2ND PLUG PULLED CASING TO 1020' & PUMPED 12 SX GEL & 50 SX CMT. 3RD PLUG PULLED CASING TO 380' & PUMPED 50 SX CMT. 4TH PLUG PULLED CASING TO 35' & PUMPED 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4203	4211		ARBUCKLE

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Eric MacLaren

RECEIVED

DEC 12 2011

KCC DODGE CITY

(TECHNICIAN)

RECEIVED

DEC 13 2011

KCC WICHITA

FORM CP 273

12/16/11