

TO: STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-031-21410-00-00
Spot: SESWNE Sec/Twnshp/Rge: 11-21S-14E
2310 feet from N Section Line, 1650 feet from E Section Line
Lease Name: CRAIG Well #: 10
County: COFFEY Total Vertical Depth: 1939 feet

Operator License No.: 5420
Op Name: WHITE & ELLIS DRILLING, INC.
Address: PO BOX 48848
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	69		
PROD	5.5	1938		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/07/2011 8:00 AM
Plug Co. License No.: 6527 Plug Co. Name: TITUS WELL SERVICE
Proposal Rcvd. from: DALLAS FLOWERS Company: _____ Phone: (316) 321-0550

Proposed Plugging Method: 50' cement plug @ 1900' 50' cement plug @ 900' 250' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 12/07/2011 11:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1900' pumped 15 sxs. Cement, pulled tubing to 900' pumped 15 sxs. Cement, pulled tubing to 270' pumped 53 sxs. Cement to surface, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1938	1939		

RECEIVED
DEC 12 2011
KCC Chanute Dist. #3
MH

RECEIVED
DEC 15 2011

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Mike Deffen
(TECHNICIAN)

12/16/11