

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02031-00-00
Spot: SENENE Sec/Twnshp/Rge: 24-19S-6W
4241 feet from S Section Line, 449 feet from E Section Line
Lease Name: SPOHN Well #: 3
County: RICE Total Vertical Depth: 3459 feet

Operator License No.: 32081
Op Name: SMOKEY VALLEY RESOURCES, INC.
Address: 6604 TARRYTOWN ST
PARK CITY, KS 67219

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	181		125 sxs
PROD	5	3459	1240	100 sxs

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/10/2011 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2011 12:15 PM KCC Agent: SHANE JONES

Actual Plugging Report:
GEORGE SALING DROPPED SAND. 11/9/11 KELSO'S TAGGED SAND @ 3167' AND CAPPED W/5SX. THEY RIPPED CASING @ 1240'. 11/10/11 KELSO PULLED CASING TO 850'. COPELAND TIED ON AND BROKE CIRCULATION. THEY SPOTTED 35 SX COMMON W/3% CC. KELSO'S PULLED UP TO 450' AND WAITED 1 HR. KELSO'S RAN SWAB BAR DOWN TO TAG PLUG. KELSO'S TAGGED @ 446' WHICH WAS THE BOTTOM OF THE 5/5". AFTER A FEW MINUTES BAR FELL AND PULLED OUT SLACK IN LINE. LET OFF MORE LINE AND WAS TAGGED OUT AGAIN @ 515' IT APPEARS SIDE WALLS OF HOLE ARE CAVING OFF. IT WAS DECIDED TO CIRCULATE FROM THIS POINT TO SURFACE. COPELAND TIED BACK ON, AND THEY CIRCULATED 195 SX TO SURFACE. KELSO'S PULLED THE REST OF THE CASING HOLE STANDING FULL. COPELAND TK #39365 35 SX COMMON W/3% CC AND 195 SX 60/40 POS W/4% GEL. 11/9/11 VIRGIL CLOTHIER CHECKED TOP PLUG FINDING IT AT SURFACE.


Perfs:

Top	Bot	Thru	Comments
3413	3419	CSG	

RECEIVED
DEC 15 2011
KCC WICHITA

Remarks: COMMISSION ORDER DKT #12-051 DEADLINE 11/6/11
Plugged through: CSG

District: 02

Signed  (TECHNICIAN)

✓ 12/16/11

✓ JK