

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-169-20330-00-00  
Spot: SWSENWSW Sec/Twnshp/Rge: 25-15S-4W  
1450 feet from S Section Line, 750 feet from W Section Line  
Lease Name: FROST Well #: 1  
County: SALINE Total Vertical Depth: 443 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	221		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/21/2011 10:00 AM

Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.

Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: \_\_\_\_\_

Witness Type: PARTIAL

Date/Time Plugging Completed: 11/22/2011 7:00 PM

KCC Agent: SHANE JONES

Actual Plugging Report:

Perfs:

OPERATOR SET AND CEMENTED 221' OF 8 5/8". DRILLED OUT AND LOST CIRCULATION @ 264'. THEY HAD QUALITY SQUEEZE IT OFF WITH 150 SX. THEY WENT BACK IN AND TAGGED IT AROUND 110'. THEY DRILLED DOWN TO 443' AND LOST CIRCULATION. THEY DID NOT GET CIRCULATION BACK. 11/21/11 TRIED PLUGGING WELL 4 TIMES ON USING 235 SX AND 400 BBLs OF MUD, COTTON SEED HULLS, WOOD FIBER AND OTHER FLUIDS WITH NO LUCK. 11/22/11 SOUTHWIND PUMPED 80 BBLs OF HEAVY MUD FOLLOWED BY 100 SX 60/40 POS W/4% GEL & 4% CC. THEY WAITED 1 HR AND TRIED TOPPING OFF USED 150 SX 60/40 POS 4% GEL & 4% CC. QUALITY OUT OF CEMENT. ROCK DROP SHOWS CEMENT DOWN ABOUT 1 1/2 SECONDS. QUALITY BRING OUT ANOTHER LOAD OF CEMENT. SOUTHWIND USED ANOTHER 40 SX COMMON W/4% CC AND HAD CEMENT TO SURFACE. SHUT DOWN. 11/23/2011 CEMENT DOWN 10' IN SIDE SURFACE WILL TOP OFF WHEN SET SURFACE ON THE NEW FROST #1.

Remarks:

Plugged through: OH

RECEIVED  
DEC 15 2011  
KCC WICHITA

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

✓ 12/16/11

✓