

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-01014-00-00
Spot: NWSWSENW Sec/Twnshp/Rge: 10-18S-1W
2977 feet from S Section Line, 3693 feet from E Section Line
Lease Name: TECTER Well #: 1
County: MCPHERSON Total Vertical Depth: 2692 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 10500 E BERKELEY SQ PKWY STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	252		175 SX
PROD	5.5	2677		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/30/2011 8:30 AM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: STAN MITCHELL Company: _____ Phone: (620) 272-1025

Proposed Plugging Method: AS PRE KCC

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2011 3:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

OPERATOR WAS TRYING TO SQUEEZE SOME HOLES IN THE CASING AND CEMENT CAME AROUND AND CEMENTED IN PACKER. THEY TRIED TO WASH IT DOWN BUT GAVE UP AND THEY DECIDED TO PLUG IT. JUSTIN TROUT W/HARTMAN ALLED AND GOT PLUGGING INSTRUCTIONS FROM J KLOCK DIST 2. BOTTOM OF HOLE IS SANDED OFF PACKER @ 1452' TOP OF FISH 1362'. 11/29/11 THE PERFORATORS OUT OF HAYS PERFORATED @ 300'. 11/30/11 H2 PLAINS RAN TUBING TO 1350' AND SPOTTED 35 SX OF 60/40 POS W/4% GEL. THEY THEN LAID DOWN TUBING AND TIED ON TO CASING. ALLIED TIED ON AND BROKE CIRCULATION WITH WATER. THEY SWITCHED TO CEMENT AND CIRCULATED TO SURFACE WITH 100 SX OF 60/40 POS W/4% GEL. 12/1/11 I CHECHED TOP PLUG WAS DOWN 8' PLUS INSIDE OF 5.5". THEY PULLED THE PLUGS ON THE SURFACE HEAD AND FOUND IT FULL OF CEMENT. JUSTIN TROUT ORDERED SLURRY MIX FROM CONCRETE PRODUCTS OF HILLSBORO. TOPPED OFF THE 5.5" FIRST AND THEN FILLED UP THE BACKSIDE.

Perfs:

Top	Bot	Thru	Comments
2677	2692	OH	

RECEIVED

Remarks: WORK OVER THAT WENT BAD

DEC 15 2011

Plugged through: TBG

KCC WICHITA

District: 02

Signed  (TECHNICIAN)

12/16/11