

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20383-00-00
Spot: SENENWNE Sec/Twnshp/Rge: 36-18S-1W
4693 feet from S Section Line, 1563 feet from E Section Line
Lease Name: DOLE Well #: 1
County: MCPHERSON Total Vertical Depth: 2786 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	113		100 SX
PROD	5.5	2784	1000	40 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/30/2011 8:00 AM
Plug Co. License No.: 3038 Plug Co. Name: CYCLONE WELL SERVICE, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/30/2011 9:45 AM KCC Agent: SHANE JONES

Actual Plugging Report:

11/23/11 CYCLONE MOVED IN AND LAID OUT WELL. THEY DROPPED SAND AND SHUT DOWN FOR THE HOLIDAY. 11/28/11 CYCLONE TAGGED SAND @ 2730' AND CAPPED WITH 5 SX. THEY THEN STARTED RIPPING CASING. 11/29/11 CYCLONE RIPPED CASING AT APPROX 1000' AND LAID IT OUT. THEY PLAN TO CEMENT TOMORROW @ 8:00 AM. 11/30/11 CYCLONE RAN TUBING TO 250' AS PER DISCUSSION BETWEEN J KLOCK & TERRY BANDY. COPELAND TIED ON AND BROKE CIRCULATION WITH WATER. THEY THEN SWITCHED TO CEMENT AND CIRCULATED IT TO SURFACE. CYCLONE PULLED TUBING HOLE STANDING FULL. COPELAND USED 265 SX OF 60/40 POS W/4% GEL TK #37833. 12/1/11 I CHECKED TOP PLUG FINDING IT DOWN 10'. I TALKED TO TERRY BANDY. THEY WILL DRY SACK TO SURFACE AND CUT OFF CASING.

Perfs:

Top	Bot	Thru	Comments
2784	2786	OH	

RECEIVED
DEC 15 2011
KCC WICHITA

Remarks: COMMISSION ORDER DKT #11-250 DEADLINE 11/21/11. TEPE COULD NOT GET A VALID OIL & GAS LEASE OR A FARM OUT FROM CURRENT LEASE HOLDER.

Plugged through: TBG

District: 02

Signed  (TECHNICIAN)

12/16/11

✓