

RECEIVED  
AUG 12 2003  
KCC WICHITA

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-171-20,291-00-01 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR BEREXCO INC. KCC LICENSE # 5363  
(owner/company name) (operator's)

ADDRESS P.O. BOX 20380 CITY WICHITA,

STATE KS ZIP CODE 67208 CONTACT PHONE # (316) 265-3311

LEASE BROOKOVER WELL# 7-20 SEC. 20 T. 17S R. 31 (East/West)

S/2- NW - SE SPOT LOCATION/OOOO COUNTY SCOTT

1650 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL X GAS WELL     D&A     SWD/ENHR WELL     DOCKET#    

CONDUCTOR CASING SIZE     SET AT     CEMENTED WITH     SACKS

SURFACE CASING SIZE 8 5/8" SET AT 304' CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 4031' CEMENTED WITH 675 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3979'-83' PERFS 4031'-38' OPEN HOLE

ELEVATION 2966/2971 T.D. 4038' PBDT 4038' ANHYDRITE DEPTH 2260'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR     CASING LEAK     JUNK IN HOLE    

PROPOSED METHOD OF PLUGGING SQUEEZE PERFS 2970-83' & OPEN HOLE 4031-38' W/100 SX COMMON CMT

UNDER PKR. LEAVE TOP OF CEMENT @ 3900'. CIRCULATE 2009SX 65/35 POZ W/6% GEL FROM

2290' TO SURFACE.  
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? YES

If not, explain why?    

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

WAYNE GERSTNER PHONE# (316) 772-1155

ADDRESS 808 S. HWY 83 City/State GARDEN CITY, KS 67846

PLUGGING CONTRACTOR BEREXCO INC. KCC LICENSE # 5363  
(company name) (contractor's)

ADDRESS P.O. BOX 20380 WICHITA, KS 67208 PHONE # (316) 265-3311

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 8/25/03, 9:00 AM

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8/8/03 AUTHORIZED OPERATOR/AGENT: *Erin Clayton*  
(signature)

6/04

6/04

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    John Wine, Commissioner    Robert E. Krehbiel, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Berexco, Inc.  
PO Box 20380  
Wichita, KS 67208

August 13, 2003

Re: BROOKOVER #7-20  
API 15-171-20291-00-01  
S2NWSE 20-17S-31W, 1650 FSL 1980 FEL  
SCOTT COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely



David P. Williams  
Production Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(316) 225-8888