

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 34318  
Name: Berexco, L.L.C.  
Address 1: P. O. Box 723  
Address 2: 2020 N Bramblewood, Wichita KS 67201  
City: Hays State: KS Zip: 67601 +  
Contact Person: Dennis Kirmer  
Phone: ( 785 ) 628-6101  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Lansing Depth to Top: -3969- Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Arbuckle Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. 3358  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 15-167-19358-00-01  
Spot Description: \_\_\_\_\_  
\_NW\_ NW\_ NW Sec. 21 Twp. 11 S. R. 15  East  West  
330 Feet from  North /  South Line of Section  
330 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Russell  
Lease Name: Spicer/Hines Unit Well #: 24X  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: \_\_\_\_\_ (KCC District Agent's Name)  
Plugging Commenced: 12-9-11  
Plugging Completed: 12-9-11

RECEIVED  
DEC 19 2011

KCC WICHITA

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Lansing	Oil		15 1/2	395	unknown
Arbuckle	Oil		12 1/2	572	unknown
			10	928	Unknown
			8: <u>5/8</u>	2445 <u>2970</u>	Unknown Unknown

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run 4 1/2" O.D. notched collar on 2 7/8" tubing. Circulate down to 1925'. Did not feel any casing left in hole. Rig up Allied Cementing. Spot 50 sacks 60/40 poz 4% gel w/200# hulls through tubing. Pull tubing to 1500'. Spot 100 sacks cement w/300# hulls. Pull tubing to 975'. Spot 100 sacks cement w/300# hulls. Pull tubing to 650'. Spot 100 sacks cement w/400# hulls. Pull tubing to 400'. Mix 300 sacks cement w/300# hulls. Did not get cement to surface. Pull tubing out of hole. Job finished 5:30 p.m. Witnessed by Pat Bedore-Hays KCC. NOTE: Tagged top of cement w/tubing at 80' F.S. on 12/12/11. Will top off hole w/6 yards of Redi-Mix when location dries.

Plugging Contractor License #: 34318 Name: Berexco, L.L.C.  
Address 1: P. O. Box 723 Address 2: 2020 N Bramblewood, Wichita KS 67201  
City: Hays State: KS Zip: 67601 +  
Phone: ( 785 ) 628-6101  
Name of Party Responsible for Plugging Fees: Berexco, L.L.C.  
State of Kansas County, Sedgwick, ss.  
Dennis Kirmer  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: Dennis Kirmer

AK