

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 4824  
Name: Pioneer Natural Resources USA, Inc.  
Address 1: 5205 North O'Conner Blvd  
Address 2: \_\_\_\_\_  
City: Irving State: TX Zip: 75039 + 3707  
Contact Person: Virginia Tijerina  
Phone: (972) 444-9001  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Ft Riley Depth to Top: 2716 Bottom: 2728 T.D. 2740  
Winfield Depth to Top: 2615 Bottom: 2694 T.D. 2740  
Krider Depth to Top: 2525 Bottom: 2578 T.D. 2740

API No. 15 - 15-081-00145-00-00  
Spot Description: 14 KCC 29  
SE SE SE NW Sec. 9 Twp. 30 S. R. 34  East  West  
2,440 Feet from  North /  South Line of Section  
2,540 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Haskell  
Lease Name: Yunker, E.R. Well #: 1  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: 11/09/11 (Date)  
by: Eric Maclaren (KCC District Agent's Name)  
Plugging Commenced: 11/10/11  
Plugging Completed: 11/11/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Herrington		Surface	10 3/4"	753'	NONE
Krider		Production	7"	2511'	NONE
Winfield					
Ft. Riley					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run tbg & tag top of tubing fish @ 2405'. Run 7" 10K tubing set CIBP & set @ 2349', circulate hole w/ mud & spot 50 sks cement up to 2059'. Pull up hole w/ tbg @ 1500' & spot 50 sks Class "C" cement w/ 100 lbs cottonseed hulls to cover casing leak. POH w/ tbg & WOC. Tag TOC @ 1276'. Test casing @ 500 psi. Perf squeeze holes @ 800'. RU down 7" & circulate to surface w/ 410 sks Class "C" cement w/ 2% Bentonite. Leave full to surface.

Plugging Contractor License #: 33338 Name: Orr Enterprises, Inc.  
Address 1: P. O. Box 1706 Address 2: \_\_\_\_\_  
City: Duncan State: OK Zip: 73534 + 1706  
Phone: (580) 467-0258  
Name of Party Responsible for Plugging Fees: Pioneer Natural Resources USA, Inc.  
State of Texas County, Dallas, ss.  
Virginia Tijerina  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Virginia Tijerina

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

DEC 19 2011

KCC WICHITA