

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 4824
Name: Pioneer Natural Resources USA, Inc.
Address 1: 5205 North O'Conner Blvd
Address 2: _____
City: Irving State: TX Zip: 75039 + 3707
Contact Person: Virginia Tijerina
Phone: (972) 444-9001
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Ft Riley Depth to Top: 2709 Bottom: 2742 T.D. 2747
Winfield Depth to Top: 2664 Bottom: 2690 T.D. 2766
Krider Depth to Top: 2563 Bottom: 2649 T.D. 2766

API No. 15 - 15-081-00538-00-00
Spot Description: _____
SW - SW. SW. NE Sec. 10 Twp. 30 S. R. 34 East West
2,540 Feet from North / South Line of Section
2,540 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Haskell
Lease Name: Huxman, C.L. Well #: 2
Date Well Completed: 10/17/1944
The plugging proposal was approved on: 11/07/2011 (Date)
by: Steve Durrant (KCC District Agent's Name)
Plugging Commenced: 11/07/11
Plugging Completed: 11/09/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Herrington		Surface	10 3/4"	637'	NONE
Krider		Production	7"	2528'	NONE
Winfield					
Ft. Riley					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run tbg & tag fill @ 1940' . POH w/ tbg & perf squeeze holes @ 1925' . Run tbg @ 1925' & spot 50 sks Class "C" cement up to 1635' . POH w/ tbg & PU 7" Packer & set @ 1100' . Squeeze with 60 sks Class "C" cement & displace to 1300' . WOC . Tag TOC @ 1300' . Test casing @ 400 psi . Perf squeeze holes @ 650' . RU down 7" & circulate to surface w/ 420 sks Class "C" cement w/ 2% Bentonite . Leave full to surface.

Plugging Contractor License #: 33338 Name: Orr Enterprises, Inc.
Address 1: P. O. Box 1706 Address 2: _____
City: Duncan State: OK Zip: 73534 + 1706
Phone: (580) 467-0258
Name of Party Responsible for Plugging Fees: Pioneer Natural Resources USA, Inc.
State of Texas County, Dallas, ss.
Virginia Tijerina Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Virginia Tijerina

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
DEC 19 2011
KCC WICHITA

AC