

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5208
Name: Exxon Mobil Corporation
Address 1: P.O. Box 4358
Address 2: _____
City: Houston State: TX Zip: 77210 + _____
Contact Person: Richard Redus
Phone: (281) 654-1656
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 2934' Bottom: 2984' T.D. 3065'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 189-20370 • 00 • 00
Spot Description: KCC SWNNWSE-NW
Sec. 17 Twp. 32 S. R. 36 East West
1,714 Feet from North / South Line of Section
1,390 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Stevens
Lease Name: Ratcliff Well #: 1
Date Well Completed: _____
The plugging proposal was approved on: 11/18/2011 (Date)
by: Ken Jehlik (KCC District Agent's Name)
Plugging Commenced: 11/18/2011
Plugging Completed: 11/21/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	619'	None
		Production	5 1/2"	3065'	1425'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run tbg @ 2433' & tag solid fill . RU cement trucks & circulate hole w/ mud & spot 100 sks Class "C" cement , POH w/ tbg & WOC . Tag TOC @ 1586'. Cut & pull 5 1/2" casing from 1425', (35 jts csg) . Run tbg at 650' , mix & spot 75 sks Class "C" cement up to 373' , POH w/ tbg & top out 64' - 4' w/ 20 sks cement .

Plugging Contractor License #: 33338 Name: Orr Enterprises , Inc.
Address 1: P.O. Box 1706 Address 2: _____
City: Duncan State: Oklahoma Zip: 73534 + 1706
Phone: (580) 467-0258

Name of Party Responsible for Plugging Fees: EXXONMOBIL PROD. CO.
State of KANSAS County, GRANT, ss.
OCTAVIO D. MORALES Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Octavio D. Morales

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
DEC 19 2011
KCC WICHITA

Ac