

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32475
Name: Braden Petroleum & Well Plugging
Address 1: 10139 SW Haverhill Rd.
Address 2: _____
City: Augusta State: KS Zip: 67010 + _____
Contact Person: James Braden
Phone: (620) 222-1252
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
BV Depth to Top: 2786' Bottom: 90' T.D. 2857'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 015-22839-0000
Spot Description: _____
SE NW SE Sec. 23 Twp. 28 S. R. 5 East West
1,656 Feet from North / South Line of Section
1,333 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Butler
Lease Name: North Fox Bush- Shauver Well #: 5
Date Well Completed: _____
The plugging proposal was approved on: 06/08/2011 (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 11/28/2011
Plugging Completed: 12/01/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
BV	water	Surface	8 5/8"	219'	
		Production	5 1/2"	2871'	1205'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sanded back 2735', Dumped 6 sx. cement on top of sand. Shot off 5 1/2" pipe at 1205'. Laid out pipe. Run 268' tubing inside 8 5/8" pipe circulated cement to the surface pulled tubing topped off with cement. Used 110 sx. cement on top plug. Consolidated cementing ticket # 34016.

Plugging Contractor License #: 32475 Name: Braden Petroleum & Well Plugging
Address 1: 10139 SW Haverhill Rd. Address 2: _____
City: Augusta State: Kansas Zip: 67010 + _____
Phone: (620) 222-1252
Name of Party Responsible for Plugging Fees: James Braden
State of Kansas County, Butler, ss.
James Braden Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: James R Braden

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

DEC 21 2011

KCC WICHITA