

KCC OIL/GAS REGULATORY OFFICES

Date: 11/28/11

District: 1

Case #: _____

- New Situation
- Response to Request
- Follow-Up

- Lease Inspection
- Complaint
- Field Report

Operator License No: 4767

API Well Number: 15-057-20765-00-00

Op Name: Ritchie Exploration, Inc.

Spot: NE-NW-SW Sec 18 Twp 27 S Rng 22 E / W

Address 1: 8100 E. 22nd St. N., #700

2376 Feet from N / S Line of Section

Address 2: Box 783188

960 Feet from E / W Line of Section

City: Wichita

GPS: Lat: 37.69738 Long: 99.77537 Date: 11/28/11

State: KS Zip Code: 67278 -3188

Lease Name: Henry 18BC Well #: 1

Operator Phone #: (316) 691-9500

County: Ford

Reason for Investigation:

Operator requested a state witness to the alternate II cementing job.

Problem:

Alternate II cementing requirements have not been met.

Persons Contacted:

Gary Rowe.

Findings:

8 5/8" was set @ 338' with 250 sx cement. 5 1/2" was set @ 5300' with 170 sx cement on the primary cementing job. Company opened port collar @ 1445'. Basic Energy Services, LP pumped 335 sx cement, circulating 20 sx to the pit. Closed port collar.

Action/Recommendations:

Follow Up Required Yes No

Date: _____

None. Alternate II cementing requirements have been met.
60/40 poz, 6% gel, 1/4# floesal by Basic Energy Services, LP.

Verification Sources:

Photos Taken: 0

- RBDMS
- T-I Database
- Other: On-sie witness.
- KGS
- District Files
- TA Program
- Courthouse

By: Eric MacLaren
Eric MacLaren

Retain 1 Copy District Office
Send 1 Copy to Conservation Division

RECEIVED
DEC - 2 2011
KCC DODGE CITY

RECEIVED
DEC 08 2011
KCC WICHITA