

KCC OIL/GAS REGULATORY OFFICE

15-171-20511-0000

ALT 2

DATE 3/20/97

- New Situation
- Response to Request
- Follow-up

OPERATOR Wabash Energy Corporation # 31251

NAME P.O. Box 595

LOCATION CENW&SW-rt, SEC 31, T 17 S, R 31 W

& ADDRESS Lawrenceville, IL 62439

LEASE Strickert Well # 10

PHONE NO. OPER. 618-943-3365 OTHER _____

COUNTY Scott API# 15-171-20,511-00-00

REASON FOR INVESTIGATION: Alternate II completion.

LEASE INSPECTION

PROBLEM: _____

PERSON(S) CONTACTED: _____

FINDINGS: TD @ 4670', Anhydrite depth at 2303-22', ran 14.5# 5 1/2" to 4664', DV tool at 2312',
8 5/8" at 249.54' with 180 sx cement. Cemented by Allied with 60/40 Pozmix 6% gel 3% cc.
Cemented bottom with 150 sx standard. Top stage with 390 sx Halliburton Lite, displaced
166 sx to pit. Total of 224 sx on top stage.
Started at 6 p.m. and finished at 9 p.m. on 3/20/97.

COMPLAINT

RECEIVED
KANSAS CORP COMM
1997 MAR 26 P 12:33

ACTION/RECOMMENDATIONS: _____ photos taken: _____
Alternate II cementing completed.

FIELD REPORT
X

Retain 1 copy Joint District Office
Send 1 copy Conservation Division

By Kevin Strube

3/20/97