

KCC OIL/GAS REGULATORY OFFICE

15-171-20514-00-00

ALTZ

DATE 8/20/97  
OPERATOR Wabash Energy Corporation # 31251  
NAME P.O. Box 595  
& ADDRESS Lawrenceville, IL 62439  
PHONE NO. OPER. 618 945 3365 OTHER

[X] New Situation  
[ ] Response to Request  
[ ] Follow-up

App. NW NW NW  
LOCATION SW, SEC 31, T 17 S, R 31  
LEASE Strickert SWD Well # 2  
COUNTY Scott API#15-171-20,514

REASON FOR INVESTIGATION: Alternate II cement completion

PROBLEM:

PERSON(S) CONTACTED:

FINDINGS: Anhydrite top 2299', base 2319'. Cedar Hills sand from 1900-2074'  
TD 2322', 5 1/2" at 2306', 8 5/8" at 227', PBTB 2294'.

Allied plugged rathole with 15 sx cement and mouse hole with 10 sx cement.  
Started cementing casing with 60/40 Pozmix 6% gel 1/4# floeal. Pumped 400 sx cement,  
approx. 30 sx to pit. Plug down at 7:15 p.m.

ACTION/RECOMMENDATIONS: Alternate II cementing completed. photos taken:

Retain 1 copy Joint District Office  
Send 1 copy Conservation Division

By Kevin Strube

8/20/97

08-29-97  
RECEIVED  
KANSAS CORP  
1997 AUG 21 P 12:54

LEASE INSPECTION

COMPLAINT

FIELD REPORT  
x

Randy