

15-171-20071-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 15 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name Boyer Well No. 1

Location CSE-SW Sec. 20 Twp. 17 Rge. (E) (W) 31

County Scott Total Depth 4175'

Abandoned Oil Well          Gas Well          Input Well          SWD Well          D & A X

Other well as hereafter indicated         

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza, Wichita, Kansas. License No.         

Operation Completed: Hour 10:30 PM Day 5 Month 11 Year 1974

The above well was plugged as follows:

300'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 110 Cu. Ft. cement  
thru DP from 975' to 650'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru  
DP from 310' to 235' with 30 Cu. Ft. cement. Pulled DP, set bridge @ 40' with 1/2 sack  
hulls and 10 Cu. Ft. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 11/15/74  
INV. NO. 305-W