

15-171-30004-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Cleary Petroleum, Incorporated.

Complete Address: 310 Kermac Building, Oklahoma City, Oklahoma.

Lease Name See Well No. 3

Location CSE-NE Sec. 19 Twp. 17 Rge. (E) (W) 31

County Scott Total Depth 4225

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Sargent's Casing Pulling.

Address: Box #506, Liberal, Kansas. License No. 511

Operation Completed: Hour 4:00PM Day 30 Month 11 Year 1965

The Above well was plugged as follows:

296'--8 5/8" Surface pipe, cement circulated.

4039'--5 1/2" Production casing cemented with an unknown amount.

Top perforations from 4020 to 4025.

Pumped 20 Sx. cement to 3800' (WLM). Pulled 5 1/2" to 600' and circulated

heavy gel mud using rotary mud in old pits. Pulled 5 1/2" to 540' and dis-

placed 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 270' and displaced 20 Sx.

cement thru 5 1/2". Pulled 5 1/2" set bridge @ 35' and 10 Sx. cement to bottom

of cellar.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

FILED
DATE 12-2-65
INV. NO. 2331-W

DEC 3 1965
12-09-65
CONSERVATION DIVISION
Wichita, Kansas

Signed: A. L. Nichols
Well Plugging Supervisor