


15-171-20022-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 2 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Executive Petroleum Company & Petroleum, Incorporated,

Complete Address 1007 Denver, U. S. National Center, Denver, Colorado.

Lease Name Brookover Well No. 1

Location CSE-SW Sec. 18 Twp. 17 Rge. (E) (W) 31

County Scott Total Depth 1635'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leben Drilling, Incorporated,

Address Box #186, Great Bend, Kansas. License No.

Operation Completed: Hour 4:30 AM Day 31 Month 5 Year 1969

The above well was plugged as follows:

290'--8 5/8" Surface casing, cement circulated with 235 Sx.
Top of Dakota section @ 550'.

Circulated hole with heavy mud. Pulled DP to 800' and displaced 100 Sx. cement thru
DP from 800' to 475'. Pulled DP to 300' and displaced 35 Sx. cement thru DP from
300' to 195'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/3/69
INV. NO. 9841-W

Signed: M. L. Nichols
Well Plugging Supervisor