

15-171-00076-00-00

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 26 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name D. R. Lauck Oil Company,

Complete Address: 301 South Broadway, Wichita, Kansas.

Lease Name Brookover Well No. 1

Location CSW-SE Sec. 18 Twp. 17 Rge. (E) (W) 31

County Scott Total Depth 4777'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Glenn & Smith Pipe Pulling Company,

Address: 201 East Sixth, Ellinwood, Kansas. License No. 396

Operation Completed: Hour 2:30 PM Day 23 Month 5 Year 1969

The Above well was plugged as follows:

276'--8 5/8" Surface casing, cement circulated.
4255'--5 1/2" Production casing cemented on bottom with 95 Sx. Top perforations @ 4030'.
Temperature survey @ 3768'. Hole-squeezed @ 1650' with 200 Sx. cement.
Pushed plug to 4000' and built sand bridge then set 5 Sx. cement with dump bailer.
Pulled 5 1/2" casing and squeezed well with initially 15 sacks gel and followed with 100
Sx. cement from 950' to 625' then 9 sacks gel from 625' to 335' and followed with 20
Sx. cement from 335' to 275' then 6 sacks gel from 275' to 35' and finally 10 Sx. cement
from 35' to bottom of cellar. (Mudding and cementing operations by Halliburton Services).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Dickel
Well Plugging Supervisor

DATE 5/27/69
INV. NO. 9827-4