

15-171-20049-00-00

Form CP-3
Rev. 6-4-68

KANSAS

Y

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 5 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Okmar Oil Company,
Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.
Lease Name Rodenberg Well No. 1
Location CSW-SW Sec. 17 Twp. 17 Rge. (E) (W) 31
County Scott Total Depth 4038'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Sage Drilling Company, Incorporated,
Address 500 Bitting Building, Wichita, Ks. License No. _____
Operation Completed: Hour 4:00 PM Day 3 Month 10 Year 1972

The above well was plugged as follows:

338'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement
thru DP from 1250' to 925'. Pulled DP to 365' and displaced 30 Cu. Ft. cement thru
DP from 365' to 290'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *H. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 10/5/72

INV. NO. 6427-W