

15-171-20070-00-00

KANSAS

Form CP-3  
Rev: 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 17 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Okmar Oil Company  
Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas  
Lease Name Tava Well No. 1  
Location E/2 SE SE Sec. 17 Twp. 17 Rge. (E) (W) 31  
County Scott Total Depth 4615'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Red Tiger Drlg.  
Address Wichita, Kansas License No.         
Operation Completed: Hour 12:30 P Day 14 Month 12 Year 1974

The above well was plugged as follows:

RTD 4615' 8 5/8 csg set at 331' cwc 200 sx. Flg. Mat. 50-50 poz 6% total gel.  
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 800' thru drill pipe.  
Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set  
solid br idge & 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey  
Well Plugging Supervisor

DATE 12/18/74  
INV. NO. 497-W