

15-171-00064-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 9 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name R. W. Rine Drilling Company,

Complete Address: 420 Union Center, Wichita, Kansas.

Lease Name Rodenberg Well No. 1

Location CNW-NW Sec. 16 Twp. 17 Rge. (E) (W) 31

County Scott Total Depth 4647

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Company, Incorporated.

Address: Box #221, Great Bend, Kansas. License No. 49

Operation Completed: Hour 6:00PM Day 6 Month 11 Year 1964

The Above well, was plugged as follows:

284'--8 5/8" Surface pipe, cement circulated.
4647'--5 1/2" Production casing cemented with 150 Sx. Well plugged back to
4613. Top perforations @ 4657'. Temperature survey shows cement @ 3790'.

Sanded well back to 4560' and set 5 Sx. cement with dump bailer. Pulled
5 1/2" to 660' and circulated heavy gel mud. (used 30 Sx. gel). Displaced 20
Sx. cement thru 5 1/2" @ 660'. Pulled 5 1/2" to 260' and displaced 20 Sx. cement
thru 5 1/2". Pulled 5 1/2", set bridge @ 30' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. A. Roberts
Well Plugging Supervisor

DATE 11/9/64

INV. NO. 139-W