

15-071-00023-00-00

CP-3

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

SEP 25 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Hudson Oil & Gas Company,  
Complete Address: 316 Oklahoman Bldg., 500 N. Broadway, Okla City, Okla.  
Lease Name Miller Well No. 1  
Location SE-NW Sec. 9 Twp. 20 Rge. (E) (W) 39  
County Greeley Total Depth 2835  
Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Sargents Casing Pulling Service,  
Address: 121 W. 9th, Liberal, Kansas License No. 511  
Operation Completed: Hour 11:00AM Day 20 Month 9 Year 1963

The Above well was plugged as follows:

246'--3 5/8" Surface pipe, cement circulated: -2834--4 1/2" top of perforation @ 2814 1/2.  
Displaced 20 Sx cement on bottom from 2835 to 2650. Heavy mud from 2650 to 300'. Set plug @ 300' and displaced 35 Sx cement from 300' to 200'. Heavy mud from 200' to 60'. Set 10' rock bridge and 15 Sx. cement to bottom of cellar.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 9/24/63  
INV. NO. 7991-u

Signed: W. L. Nichols  
Well Plugging Supervisor