

15-071-00022-00-01

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock,
Administrator
P. O. Box 17027
Wichita, Kansas 67217RECEIVED
STATE CORPORATION COMMISSION
NOV 16 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dorchester Exploration, Incorporated,
 Complete Address 1204 Vaughn Building, Midland, Texas.
 Lease Name Angell Well No. 1
 Location SE-SE Sec. 5 Twp. 20 Rge. (E) (W) 39
 County Greeley Total Depth 1298'
 Abandoned Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated This was an attempted wash-down, left bore hole
and abandoned.
 Plugging Contractor Sterling Drilling Company,
 Address Box #129, Sterling, Kansas. License No.
 Operation Completed: Hour 2:30 PM Day 14 Month 11 Year 1973

The above well was plugged as follows:

327'--13 3/8" Surface casing, cement circulated.
 Top of Dakota section @ 850'.

Circulated hole with heavy mud. Pulled DP to 1070' and displaced 110 Cu. Ft. cement
 thru DP from 1070' to 745'. Pulled DP to 315' and displaced 50 Cu. Ft. cement thru
 DP from 315' to 260'. Pulled DP, set bridge @ 30' with 1 sack hulls and 20 Cu. Ft.
 cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 11/16/73INV. NO. 8174-10Signed: M. L. Nichols

Well Plugging Supervisor