

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20182-00-00
Spot: CSWSWSW Sec/Twnshp/Rge: 5-20S-39W
300 feet from S Section Line, 330 feet from W Section Line
Lease/Unit Name: ANGELL Well Number: 1
County: GREELEY Total Vertical Depth: 2900 feet

Operator License No.: 7271
Op Name: BARTLING OIL COMPANY
Address: 5910 COURTYARD DR #255
AUSTIN, TX 78731

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 246 WITH 250 SX CMT
Production: Size 4.5 feet: 2899 WITH 400 SX CMT
Liner: Size feet: \$ 94.25

Well Type: GAS UIC Docket No: Date/Time to Plug: 06/06/2001 9:20 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: WARREN OCSHNER Company: BARTLING OIL Phone: (512) 795-9593

Proposed Plugging Method: 400# HULLS & CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/06/2001 10:30 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFS AT 2818-26'. PUMP DOWN 4 1/2" CASING 400# HULLS & 145 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN AT 500#. PUMP DOWN 8 5/8" X 4 1/2" ANNULUS 15 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN AT 500#.

INVOICED

DATE 6-14-01

INV. NO. 2001061949

RECEIVED

KANSAS CORPORATION COMMISSION

JUN 14 2001

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERE.

CONSERVATION DIVISION

Plugged through: CSG

District: 01

Signed

Kevin D. Strube

(TECHNICIAN)
JUN 12 2001

Form CP-2/3