

1060817

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 203-20,085 -00 -00

C NW NW , SEC. 14 , T 16 S, R 36 (W/B)

4620 feet from S section line

4620 feet from E section line

Omaha Hotel,

Lease Name Inc. Well # 1-14

TECHNICIAN'S PLUGGING REPORT

Operator License # 5652

Operator: Mustang Drilling & Exploration, Inc.
Name: P. O. Box 1609
Address: Great Bend, KS 67530

County: Wichita 162.79

Well Total Depth 5009 Mississippi feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 477

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Mustang Drilling & Exploration, Inc. License Number 5652

Address P. O. Box 1609, Great Bend, KS 67530

Company to plug at: Hour: 11:00 pm Day: 27 Month: February Year: 19 86

Plugging proposal received from Bill Nelson

(company name) Mustang (phone) 316-792-7323

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2533 base

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:00 am Day: 28 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2542' with 50 sx cement, 2nd plug at 1550' with 80 sx cement, 3rd plug at 500' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAR 4 1986

Remarks: Used 60/40 Pozmix 6% gel

(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE MAR 04 1986

INV. NO. 12850
2-28

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date March 31, 1986 month day year

API Number 15- 203-20,085-00-00 East

OPERATOR: License # 5652 Name Mustang Drilling & Exploration, Inc. Address P. O. Box 1609 City/State/Zip Great Bend, KS 67530 Contact Person James Meroney Phone 316-792-7323

C. NW. NW. Sec. 14. Twp. 16. S. Rg. 36. 4620 Ft. from South Line of Section 4620 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5652 Name Mustang Drilling & Exploration, Inc. City/State Great Bend, Kansas 67530

Nearest lease or unit boundary line 660 feet

County Wichita

Lease Name Omaha Hotel, Inc. Well # 1-14

Ground surface elevation feet MSL

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl X Wildcat Cable

Domestic well within 330 feet: yes X no

Municipal well within one mile: yes X no

Surface pipe by Alternate: 1 1/2 X

Depth to bottom of fresh water 250

Depth to bottom of usable water 1400-1500

Surface pipe planned to be set 450

Projected Total Depth 4950 feet

Formation Mississippi

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

YES cementing will be done immediately upon setting production casing.

Date 1-3-86 Signature of Operator or Agent Title Exploration Manager

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per Alt. (2)

This Authorization Expires 7-9-86 Approved By 1-9-86

5 ft 450' at 5/8" on 2/16/86

Will call back for plug orders Bill Melton

TD FORMATION SURFACE PIPE 8 3/8 @ 477 ANHYDRITE ELEVATION STARTING TIME & DATE COMPLETION TIME & DATE 1st PLUG @ FT. W/ SX 2nd PLUG @ FT. W/ SX 3rd PLUG @ FT. W/ SX 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATED W/ SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ SX CEMENT COMPANY

1st plug base Andy 5-0 2nd base Cheyane w/ 80 3rd 30' out surf w/ 40 40-0 S B P w/ 10 air 15' mat 60/40 w/ 6/0

RECEIVED STATE CORPORATION COMMISSION

MAR 4 1986

CONSERVATION DIVISION Wichita Kansas