

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-203-20076-00-00
SE4, Sec. 22, T 16 S, R 37 W/E
660 feet from N/S section line
1980 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Eugene Well # 1-22

Operator: Geor pet Co. Inc
Name & 300 Sutter place
Address Wichita Ks 67202

County Wichita

Well Total Depth 5080 feet 165.10

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 428

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor MURFIN Drilling License Number 6033

Address 617 Union Center Bldg Wichita Ks 67202

Company to plug at: Hour: 9:00am Day: 10 Month: Jan Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO McRae

(company name) MURFIN Drilling (phone)

were: Heavy mud to 2540' c/c, 50 sy Cement at 2540' mud
1200' 50 sy Cement mud to 475' 50 sy Cement mud to
40' solid bridge 10 sy Cement to Surface, 15 sy Cement in
Rothole 10 sy Cement in mousehole 60/40 pay 29 gal 39 cc.

Signed J. A. Troy (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:00pm Day: 10 Month: Jan Year: 1984

ACTUAL PLUGGING REPORT Heavy mud to 2540' c/c 50 sy Cement at 2540'
mud to 1200' 50 sy Cement mud to 475' 50 sy Cement mud
to 40', 10 sy Cement to Surface, 15 sy Cement in Rothole
10 sy Cement in mousehole

Remarks: Cemented by Sun

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

RECEIVED STATE CORPORATION COMMISSION

JAN 18 1984

CONSERVATION DIVISION Wichita, Kansas

INVOICED

DATE 1-20-84

INV. NO. 9205-W

Signed J. A. Troy (TECHNICIAN)

FORM CP-2/3 Rev. 9-82