

1 090150

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-203-20,079-00-00

SW NE SW, SEC. 7, T 17 S, R 36 W X

1650 feet from W/S section line

1650 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5290

Lease Name Kalbach Well # 1

Operator: Hinkle Oil Company

County Wichita

Name & Address 1016 Union Center Building

Well Total Depth 5040 16880 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 391

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center Building, Wichita, KS 67202

Company to plug at: Hour: 9:00 am Day: 7 Month: April Year: 19 84

Plugging proposal received from Wally Towns

(company name) Abercrombie Drilling (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2460' with 50 sx cement 2nd plug at 1620' with 50 sx cement

3rd plug at 900' with 50 sx cement 4th plug at 450' with 40 sx cement  
solid bridge

5th plug hulls - plug at 40' -- cement to surface with 10 sx cement

7th plug to circulate rathole with 15 sx cement

8th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by: R. Barluttan (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:15 am Day: 7 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2460' with 50 sx cement, 2nd plug at 1620' with 50 sx cement, 3rd plug at 900' with 50 sx cement, 4th plug at 450' with 40 sx cement

5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement. 7th plug to circulate rathole with 15 sx cement, 8th plug to circulate mousehole with 10 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun No. 17156

(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 4-12-84

Signed R. Barluttan (TECHNICIAN)

INV. NO. 1139

RECEIVED STATE CORPORATION COMMISSION

APR 12 1984

CONSERVATION DIVISION Wichita, Kansas

4-7