

1 050204

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 203-20,078 -00-60

SW SE SE, SEC. 5, T 17 S, R 36 WSE

330 feet from N/S section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5290

Lease Name Whitham Well # 1

Operator: Hinkle Oil Company

County Wichita

Name & Address 1016 Union Center Building

Well Total Depth 4845 157.47 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 395

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5244

Address 801 Union Center Building, Wichita, KS 67202

Company to plug at: Hour: 5:00 am Day: 27 Month: April Year: 19 84

Plugging proposal received from Wally Towns

(company name) Abercrombie Drilling (phone) 913-462-2123

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2470' with 50 sx cement 2nd plug at 1400' with 50 sx cement

3rd plug at 700' with 50 sx cement 4th plug at 420' with 40 sx cement
solid bridge

5th plug hulls - plug at 40' -- cement to surface with 10 sx cement

7th plug to circulate rathole with 15 sx cement

8th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:15 am Day: 27 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2470' with 50 sx cement, 2nd plug at 1400' with 50 sx

cement, 3rd plug at 700' with 50 sx cement, 4th plug at 420' with 40 sx cement, 5th &

6th plugs - solid bridge- hulls - plug at 40' -- cement to surface with 10 sx cement,

7th plug to circulate rathole with 15 sx cement, 8th plug to circulate mousehole with

10 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun

(If additional description is necessary, use BACK of this for CONSERVATION DIVISION

INVOICED

DATE 5-4-84

INV. NO. 1385

4-27

MAY 18 1984

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAY 03 1984

CONSERVATION DIVISION
Wichita, Kansas