

1080217

TO: STATE CORPORATION COMMISSION

9-30

API NUMBER 15-203-20,035 -00-00
SE NE SW SEC. 36, T 17 S, R 37 W

CONSERVATION DIVISION - PLUGGING SECTION 1405 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2490 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME LINDBERG WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY WICHITA

OPERATOR LICENSE # 100 WELL TOTAL DEPTH 3130 FEET

OPERATOR: KCC FEE FUND #9900-21-001 PRODUCTION CSG: SIZE 4 1/2 " FEET 3130

NAME AND ADDRESS 130 S MARKET RM 2078 SURFACE CASING: SIZE 8 5/8 " FEET 341'

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING COMPANY, INC LICENSE NUMBER N/A

ADDRESS PO BOX 628, GREAT BEND, KS 67530

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 29 MONTH: 09 YEAR: 1998
HOUR: 8:30 AM DAY: 30 MONTH: 09 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KEVIN STRUBE

(COMPANY NAME) KCC (PHONE) 316-225-8888

WERE: PERFS AT 2712-90

PUMP 400# HULLS, 20 SX CEMENT, DISPLACE TO 2650'. PERFORATE @ 1500', PUMP 80 SX OVER

CASING VOLUME. PRESSURE TEST 8 5/8" X 4 1/2" ANNULAS TO 500# WITH 50 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:00 AM DAY: 29 MONTH: 09 YEAR: 1998
HOUR: 9:45 AM DAY: 30 MONTH: 09 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG ALLIED PUMPED 200# HULLS, 25 SX CEMENT, DISPLACED TO 2350'. MAXIMUM PSI PRESSURE 1000#. SHUT IN @ 500#. LOG-TECH OF KANSAS PERFORATED AT 1500' WITH 2 HOLES.

2ND PLUG ON 9/30/98 ALLIED PUMPED DOWN 4 1/2" CASING, TOOK INJECTION RATE OF 2 BBL PER MINUTE @ 600#. STARTED CEMENT, 60/40 6% , PUMPED 150 SX. 1000# MAXIMUM PRESSURE SHUT IN AT

300#. 3RD PLUG PUMPED 100 SX CEMENT DOWN 8 5/8" X 4 1/2" ANNULAS. SHUT IN AT 100# CHECKED 4 1/2" AND TOPPED OFF WITH 5 SX.

REMARKS: TOTAL CEMENT: 25 SX ON BOTTOM & 255 SX ON REMAINDER OF PLUG.
USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin P Strube (TECHNICIAN) FORM CP-2/3

RECEIVED
OCT 3 1998
CONSERVATION DIVISION
Wichita, Kansas
12-31-98