

1080218

TO:
STATE CORPORATION COMMISSION

9-30

API NUMBER 15-203-20,036-0000
NW SW SE SEC. 31, T 17 S, R 38 W

CONSERVATION DIVISION - PLUGGING SECTION 1200 FEET FROM SOUTH SECTION LINE
WICHITA STATE OFFICE BLDG., 130 S. MARKET 2440 FEET FROM EAST SECTION LINE
WICHITA, KANSAS 67202 LEASE NAME BLOEDORN WELL # 1
TECHNICIAN'S PLUGGING REPORT COUNTY WICHITA
OPERATOR LICENSE # 100 WELL TOTAL DEPTH 3240 FEET
OPERATOR: KCC FEE FUND #9900-19-001 PRODUCTION CSG: SIZE 4 1/2 " FEET 3240
NAME AND 130 S MARKET RM 2078 SURFACE CASING: SIZE 8 5/8 " FEET 340'
ADDRESS WICHITA, KS 67202
ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A
OTHER WELL AS HEREINAFTER INDICATED
PLUGGING CONTRACTOR ALLIED CEMENTING COMPANY, INC LICENSE NUMBER N/A
ADDRESS PO BOX 628, GREAT BEND, KS 67530
COMPANY TO PLUG AT: HOUR: 10:45 AM DAY: 29 MONTH: 09 YEAR: 1998
HOUR: 10:30 AM DAY: 30 MONTH: 09 YEAR: 1998
PLUGGING PROPOSAL RECEIVED FROM KEVIN STRUBE
(COMPANY NAME) KCC (PHONE) 316-225-8888

WERE: PERFS AT 2815-19 & 3054-3135

PUMP 400# HULLS, 20 SX CEMENT, DISPLACE TO 2765'. PERFORATE @ 1500', PUMP 80 SX OVER
CASING VOLUME. PRESSURE TEST 8 5/8" X 4 1/2" ANNULAS TO 500# WITH 50 SX CEMENT. RESTORE LOCATION
PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE
OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 29 MONTH: 09 YEAR: 1998
HOUR: 11:45 AM DAY: 30 MONTH: 09 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG ALLIED PUMPED 300# HULLS, 25 SX CEMENT, DISPLACED TO 2350'. MAXIMUM PSI PRESSURE
1000#. SHUT IN AT 500#. LOG-TECH OF KANSAS PERFORATED AT 1500' WITH 2 HOLES.
2ND PLUG ON 9/30/98 ALLIED PUMPED DOWN 4 1/2" CASING, TOOK INJECTION RATE @ 3 1/2 BBL PER MINUTE
@ 500#. STARTED CEMENT, 60/40 6% , PUMPED 165 SX. 500# MAXIMUM PRESSURE. SHUT IN AT
100#. 3RD PLUG PUMPED 100 SX CEMENT DOWN 8 5/8" X 4 1/2" ANNULAS. SHUT IN AT 100#

REMARKS: TOTAL CEMENT: 25 SX ON BOTTOM & 265 SX ON REMAINDER OF PLUG.
USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I (DID) OBSERVE THIS PLUGGING.

SIGNED

(TECHNICIAN)

FORM CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
Wichita, Kansas
JAN 31 1998
CONSERVATION DIVISION

12-31-98