

4-30-84

(303)-861-4246

1050122

5-9-84 To: Will call Back - OK D.K.

API NUMBER 15- 071- 20,313-00-00

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE SW NW , Sec. 1 , T 16 S, R 43 (W) X

1650 feet from N/X section line

990 feet from W/X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Edsall Well # F2

Operator: TXO Production Corp.  
Name & 1800 Lincoln Center Building  
Address Denver, CO 80264

County Greeley

Well Total Depth 5500 feet 178.75

Conductor Pipe: Size \_\_\_\_\_ feet \_\_\_\_\_

Surface Casing: Size 8 5/8 feet 452

316-265-9441

Gary Wurdeman

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Gibson JW Well Service License Number 5866

Address Aurora, CO 80010

Company to plug at: Hour: 3:00 pm Day: 21 Month: January Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Frank Tsuruta

(company name) Gibson (phone) 303-86104246

were: to fill hole with heavy mud and spot cement through dripl pipe.

1st plug at 2200' with 50 sx cement

2nd plug at 1400' with 40 sx cement

3rd plug at 500' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement.

6th plug to circulate 15 sx cement in the rathole. 7th plug to circulate mousehole with 10 sx cement.

Signed Richard M. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:30 pm Day: 21 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement, 2nd plug at 1400' with 40

sx cement, 3rd plug at 500' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement. 6th plug to circulate 15 sx cement

in the rathole. 7th plug to circulate mousehole with 10 sx cement.

Remarks: Use 60/40 Pozmix by Dowell

RECEIVED  
STATE CORPORATION COMMISSION

FEB 02 1984  
02-02-1984  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated

and that I (~~xxx~~ / did not) observe this plugging.

Signed Richard M. Lacey  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82

Final Letter  
JUL 17 1984

INVOICED

DATE 2-6-84

INV. NO. 0081

1-21

8d