

To: 1 051665
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-14

API NUMBER 15- 071-20,363-00-00

SE SE SE, SEC. 1, T. 16 S, R. 43 W/E
330 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30689

Lease Name Edsall "F" Well # 3
County Greeley

Operator: Marathon Oil Company
Name & Address P.O. Box 2690
Cody, WY 82414

Well Total Depth 5280 171.60 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 475

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Gibson Well Service License Number 5866
Address Cheyenne Wells, CO

Company to plug at: Hour: _____ Day: 29 Month: 3 Year: 19 93

Plugging proposal received from Jéannie Miskimin
(company name) Marathon Oil Co. (phone) 307-587-4961

were: 4 1/2" at 5278' w/200 sx cement, PBDT 5233', Perfs at 5125-38, 5154-64',
DV at 1799' w/150 sx cement, Est. TOC @ 1050'
1st plug set cement retainer at 5051', with 40 sx cement squeezed through retainer,
2nd plug pump 120 sx cement at 3955',
3rd plug pump 50 sx cement at 2767', 4th plug pump 125 sx cement at 707', 5th plug pump 10 sx
cement at 30'.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None
Operations Completed: Hour: _____ Day: 14 Month: 4 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set cement retainer at 5051', squeezed through retainer
with 40 sx cement,
2nd plug pumped 120 sx cement at 3955',
3rd plug pumped 50 sx cement at 2767',
4th plug pumped 125 sx cement at 707',
5th plug pumped 10 sx cement at 30'.

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1993
06-10-1993
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Gibson. Recovered 640' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (xxx / did not) observe this plugging.

Signed Richard M. Lacey
(TECHNICIAN)

INVOICED
DATE 6-11-93
INV. NO. 37881