

1 030517

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,383-00-00

NE NE SE , SEC. 1 , T 16 S, R 43 W/EX

2310 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Edsall "F" Well # 6

Operator: TXO Production Corp.

County Greeley 172.25

Name & Address 1800 Lincoln Center Building

Well Total Depth 5300 Morrow feet

Dénver, CO 80264

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 388

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 2:00 am Day: 13 Month: September Year: 19 85

Plugging proposal received from Frank Tsuru

(company name) TXO (phone) 303-861-4246

Elevation N/A

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2767'

1st plug at 2770' with 50 sx cement

2nd plug at 1660' with 50 sx cement

3rd plug at 700' with 40 sx cement

4th plug at 380' with 40 sx cement

solid bridge

5th plug hulls - plug at 40' -- cement to surface with 10 sx cement

7th plug to circulate rat hole with 10 sx cement, 8th plug to circulate mouse hole with 5

sx cement Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 4:00 am Day: 13 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2770' with 50 sx cement, 2nd plug at 1660' with 50 sx

cement, 3rd plug at 700' with 40 sx cement, 4th plug at 380' with 40 sx cement, 5th & 6th

plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 7th plug

to circulate rat hole with 10 sx cement, 8th plug to circulate mouse hole with 5 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 3% gel by Halliburton

(If additional description is necessary, use BACK of this form.)

SEP 23 1985  
09-23-1985  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

(If you did not observe this plugging.

DATE SEP 25 1985

Signed Steve Durrant  
(TECHNICIAN)

INV. NO. 10266

9-1 OCT 09 1985

FORM CP-2/3  
Rev. 01-84