

1080268

TO: STATE CORPORATION COMMISSION

9-28

API NUMBER 15-071-20,390-00-00
NE SE SE SEC. 1, T 16 S, R 43 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME EDSALL F WELL # 7

TECHNICIAN'S PLUGGING REPORT

COUNTY GREELEY

17225

OPERATOR LICENSE # 3273

WELL TOTAL DEPTH 5300 FEET

OPERATOR: HERMAN L. LOEB PRODUCTION CSG: SIZE 4 1/2" @ 5300' WITH 200 SX

NAME AND ADDRESS PO BOX 524 SURFACE CASING: SIZE 8 5/8" @ 476' WITH 230 SX

ADDRESS LAWRENCEVILLE, IL 62439

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MULL DRILLING COMPANY INC LICENSE NUMBER 5144

ADDRESS PO BOX 2758 WICHITA, KS 67201-2758

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 28 MONTH: 09 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM M.L. COX

(COMPANY NAME) MULL DRILLING COMPANY INC. (PHONE) 316-264-6366

WERE: PERFS AT 5116-31 DV @ 2823' WITH 350 SX LITE. TOP OF CEMENT AT 1818'.

PROPOSED SAME AS ACTUAL METHOD OF PLUGGING.

INVOICED

DATE 10-26-99

INV. NO. 60746

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 28 MONTH: 09 YEAR: 1999

ACTUAL PLUGGING REPORT RAN TUBING AND PACKER TO 2452'. RAN INJECTION RATE 4 BPM @ 500#.

TESTED ANNULUS TO 500# AND HELD. PUMPED DOWN TUBING 100 SX CEMENT WITH 200# HULLS. PULLED

TUBING & PACKER. PEAK WIRELINE SET CIBP @ 2000' & PERFORATED @ 1550'. BASE OF DAKOTA, RUN

TUBING IN HOLE OPEN ENDED TO 1540' PUMPED 90 SX CEMENT CIRCULATED TO SURFACE, PULLED TUBING

UP TO 350' PUMPED 20 SX CEMENT AT SURFACE, PULLED TUBING OUT OF HOLE, SQUEEZED DOWN 4 1/2 70

SX CEMENT. WELL ON VACUUM. PUMPED DOWN 8 5/8" X 4 1/2 ANNULUS 100 SX CEMENT SHUT IN AT 50#.

TOP OFF WITH 50 SX CEMENT DOWN 4 1/2.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

RECEIVED STATE CORPORATION COMMISSION

SIGNED

Kevin D. Strube (TECHNICIAN)

OCT 13 1999
10-13-1999
CONSERVATION DIVISION
Wichita, Kansas