

1080275

TO: STATE CORPORATION COMMISSION

AP NUMBER 15-071-20,426 -00-00
NE SE SW SEC. 1, T 16 S, R 43 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME EDSALL F WELL # 17

TECHNICIAN'S PLUGGING REPORT

COUNTY GREELEY *172.25*

OPERATOR LICENSE # 3273

WELL TOTAL DEPTH 5300 FEET

OPERATOR: HERMAN L. LOEB

PRODUCTION CSG: SIZE 4 1/2" @ 5300' WITH 200 SX

NAME AND PO BOX 524

SURFACE CASING: SIZE 8 5/8" @ 419' WITH 225 SX

ADDRESS LAWRENCEVILLE, IL 62439

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR MULL DRILLING COMPANY INC LICENSE NUMBER 5144

ADDRESS PO BOX 2758 WICHITA, KS 67201-2758

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 18 MONTH: 10 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM M.L. COX

(COMPANY NAME) MULL DRILLING COMPANY INC. (PHONE) 316-264-6366

WERE: PERFS AT 5138-44 DV TOOL @ 1829' W/ 350 SX CEMENT. CEMENT TOP AT 328'

CASING BAD AT 2150' COULDN'T GET DOWN AND HOLE WOULDN'T LOAD WITH WATER. SET CIBP @ 2000'

LOADED HOLE WITH FRESH WATER. HOLE STAYED LOADED. RAN BOND LOG. TOP OF CEMENT AT 328'.

RAN TUBING TO 1981'. PUMPED 100 SX CEMENT CIRCULATED TO SURFACE. PULLED TUBING TO 600'.

PUMPED 20 SX CEMENT. PULLED TUBING OUT OF HOLE AND TOPPED OFF WITH 5 SX CEMENT. PUMPED

DOWN 8 5/8" X 4 1/2" ANNULUS 0 SX CEMENT. SHUT IN AT 500#.

INVOICED

10-29-99

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

DATE 10-29-99 PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 3:00 PM DAY: 18 MONTH: 10 YEAR: 1999

ACTUAL PLUGGING REPORT CASING BAD AT 2150' COULDN'T GET DOWN & HOLE WOULDN'T LOAD W/

WATER. PEAK WIRELINE SET CIBP @ 2000'. LOADED HOLE WITH FRESH WATER. HOLE STAYED LOADED.

RAN BOND LOG. TOP OF CEMENT AT 328'. RAN TUBING TO 1981'. ALLIED PUMPED 100 SX CEMENT.

CIRCULATED TO SURFACE. PULLED TUBING TO 600' AND PUMPED 20 SX CEMENT. PULLED TUBING OUT OF

HOLE AND TOPPED OF WITH 5 SX CEMENT. PUMPED DOWN 8 5/8 X 4 1/2 ANNULUS 0 SX CEMENT. SHUT IN AT

KANSAS CORPORATION COMMISSION

500#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED

Kevin D. Strube
(TECHNICIAN)

FORM CP-2736
WICHITA, KS

OCT 22 1999
10-22-1999
[Signature]