



15-071-20024-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Sargent of Sargent's Casing Pulling Ser. has this date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Dorchester Exploration, Incorporated,

Complete Address: 1204 Vaughn Building, Midland, Texas.

Lease Name: Kerr Well No. 1

Location: CSE/4 Sec. 13 Twp. 20 Rge. (E)(W) 41

County: Greeley Total Depth 2925' Oil Well

Gas Well X Input Well  SWD Well  D & A  Lost Hole

Mr. Sargent was instructed to plug the well as follows:

352'--10 3/4" Surface casing, cement circulated with ?? (7 7/8" Hole).  
2924'--4 1/2" Production casing cemented on bottom with 175 Sx.

Squeeze bottom with 1 sack hulls followed with 20 Sx. cement. Shoot ?  
pull 4 1/2" casing to 360' and displace 50 Sx. cement thru 4 1/2" well 4 1/2",  
set bridge @ 40' with 1 sack hulls and 15 Sx. cement to bottom of cellar.

Very truly yours,

*[Signature]*

Conservation Division Agent

RECEIVED  
FEB 4 1974  
CONSERVATION DIVISION  
WICHITA, KANSAS  
STATE CORPORATION COMMISSION