



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 25 1963  
 09-25-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Bob Sargent of Sargent's Csg Pulling Serv has this

date requested permission to plug the following described well:  
Hadson Oil & Gas Co.

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Hadson Oil & Gas Company

Complete Address: 316 Oklahoman Building, Oklahoma City, Okla.

Lease Name: Miller Well No. 1

Location: SE-NW Sec. 9 Twp. 20 Rge. (E) (W) 39

County Greeley Total Depth 2835 Oil Well

Gas Well X Input Well  SWD Well  D & A  Lost Hole

Mr. Sargent was instructed to plug the well as follows:

246'--8 5/8" Surface pipe, cement circulated.

2834'--4 1/2" production casing. Top of perforations @ 2814.

Displace 20 Sx cement in bottom of well, fill hole with heavy  
mud to 300', Set plug and displace 35 Sx cement. Heavy mud  
to 60', set plug and bridge and 15 Sx cement to bottom of cellar.

Very truly yours,

M. A. Nichols  
 Conservation Division Agent