



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

NOV 16 1973

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ray Rice of Sterling Drilling Company has this

date requested permission to plug the following described well:

Mr. Rice guarantees payment of the plugging fee.Operator's full Name: Dorchester Exploration, Incorporated,Complete Address: 1204 Vaughn Building, Midland, Texas.Lease Name: Angell Well No. 1Location: SE-SE Sec. 5 Twp. 20 Rge. (E)(W) 39County: Greeley Total Depth 1298' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Rice was instructed to plug the well as follows:327'--13 3/8" Surface casing, cement circulated.Top of Dakota section @ 850'. This was an attempted wash-down, bit left original hole--abandoned.Circulate hole with heavy mud. Pull DP to 1070' and displace 110 Cu. Ft. cement thru DP. Pull DP to 315' and displace 50 Cu. Ft. cement thru DP. Pull DP, set bridge @ 30' with 1 sack hulls and 20 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent