



15-203-20064-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

RECEIVED
STATE CORPORATION COMMISSION

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

FEB 10 1962
02-10-82

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Bot. Spencer of Abercrombie Pkg. (Rigs) has this

date requested permission to plug the following described well:

Operator's Full Name: Energy Exploration Inc.

Complete Address: 120 South Market #606 Wichita, Mo 67202

Lease Name: Logan Well No. "A" - #1

Location: C-SW-SW Sec. 5 Twp. 16 Rge. 36 (E) (W)

County: Wichita Total Depth: 5628 ^{ft}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: Lost Circulation @ 3595' - 5262' - Abandoned
5257' - 5628' - and plugged.

Mr. Spencer was instructed to plug the well as follows:

Lost Circulation several times - got circulation back and
decided to Plug @ 5628^{ft} Couldn't get down beyond 2604^{ft}
according to Geologist Melvyn Thomas.

8 7/8" 456^{ft} sp. cur. w/ 300st cut. Connex - 2% Gel. - 3% Ca. Cl.

spot with Drill Stem - with heavy mud, Between all Plug.

ordered - 255st 50st Poz. 4% Gel. - 3% Ca. Cl. + 8 7/8" Plug.

- 1st Plug @ 2604^{ft} w/ 75st cut.
- 2nd Plug @ 1395^{ft} w/ 105st cut.
- 3rd Plug @ 450^{ft} w/ 50st cut.
- 4th Plug Sided Bridge @ 40^{ft} w/ 10st cut.
- 10st In Rat Hole (cir)
- 5st In Mouse Hole (cir)

Very truly yours, (By Sign Cut)

Marion Schmidt
Conservation Division Agent