



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

RECEIVED
STATE CORPORATION COMMISSION

JUN 22 1960

CONSERVATION DIVISION
Wichita, Kansas

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date June 7, 1960, authorized the following plugging operation:

Operator's Full Name: Anadarko Prod Co

Complete Address: Liberal Kans.

Lease Name: Honeywell Well No. 1

Location: 1980n1-660'e1 Sec. 7 Twp. 16 Rge. 37 (E) (W)

County: Wichita Total Depth: 5800

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

Jet pits cir hole with heavy mud, displace 25 sax cement at 5400' thru
drill pipe, displace another 50 sax cement at 2670' heavy mud to
460' and displace another 35 sax cement, heavy mud to 240' and displace
35 sax cement mud to 40' and displaced 15 sax cement cementing to
base of cellar.

Very truly yours,
Gilbert P. Leiker

Signed: Gilbert P. Leiker
 Conservation Division Agent