

State of Kansas



15-203-20020-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION

APR 1 - 1974

CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Carroll Flemmons of Galaxy Oil Company has this date requested permission to plug the following described well:

Mr. Flemmons guarantees payment of the plugging fee.

Operator's full Name: Galaxy Oil Company,

Complete Address: 918 Lamar Street, Wichita Falls, Texas.

Lease Name: Lewis Well No. 1

Location: CSE-SE Sec. 22 Twp. 16 Rge. (E)(W) 37

County: Wichita Total Depth 3258' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Flemmons was instructed to plug the well as follows:

309'--8 5/8" Surface casing, cement circulated with 200 Sx. 3258'--4 1/2" casing cemented on bottom with 160 Sx. Top perforations from 2867' to 2878'.

Set bridge plug below top of cement with 10' cement on top. Shoot off 4 1/2" casing, pull 1 joint and displace cement thru 4 1/2" to base of surface casing. Pull 4 1/2", set bridge and 10' cement to bottom of cellar.

Very truly yours,

W. L. Nichols Conservation Division Agent