



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission
CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

RECEIVED
 STATE CORPORATION COMMISSION

JUN 24 1959

CONSERVATION DIVISION
 Wichita, Kansas

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date June 15, 1959, authorized the following plugging operation:

Operator's Full Name: Philips Pet Co

Complete Address: 601 Park Blvd Wichita Kan.

Lease Name: Bauch Well No. 1

Location: C New Se Sec. 32 Twp. 16 Rge. 38 (E) (W)

County: Wichita Total Depth: 5338

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: Dry Hole

Operator was instructed to plug well as follows:

Run pits circulate hole with heavy mud, set cementing plug at 600 ft.
 and displace 20 sac cement thru drill pipe, heavy mud to 200 ft.
 set cementing plug and displace 15 sac cement, heavy mud to 40 ft.
 set and tie cementing plug in place, dump 1/2 sac hulls, and displace
10 sac cement cementing to base of cellar.

Very truly yours, Gilbert P. Leiker

Signed: Gilbert P. Leiker
 Conservation Division Agent