



15-203-20019-00-00
State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1973

03-23-73

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Virgil Shawn of Sage Drilling Company, Inc., has this
date requested permission to plug the following described well:

Mr. Shawn guarantees payment of the plugging fee.

Operator's full Name: Galaxy Oil Company,

Complete Address: 918 Lamar Street, Wichita Falls, Texas.

Lease Name: Smades Well No. 1

Location: CSE-SE Sec. 15 Twp. 17 Rge. (E)(W) 36

County: Wichita Total Depth 3050' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Shawn was instructed to plug the well as follows:

307'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 900'.

Circulate hole with heavy mud. Pull DP to 1125' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 315' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent