

State of Kansas



15-203-20016-00-00

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION

APR 1 - 1974

CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Carroll Flemmons of Galaxy Oil Company has this  
date requested permission to plug the following described well:Mr. Flemmons guarantees payment of the plugging fee.Operator's full Name: Galaxy Oil Company,Complete Address: 918 Lamar Street, Wichita Falls, Texas.Lease Name: Flatland Farms Well No. 1Location: C. NE NE Sec. 26 Twp. 17 Rge. (E)(W) 38County: Wichita Total Depth 2910' Oil Well Gas Well  Input Well  SWD Well  D & A X Lost Hole Mr. Flemmons was instructed to plug the well as follows:322'--10 3/4" Surface casing, cement circulated.2818'--7" Production casing cemented on bottom with 125 Sx. Open hole completion.Set 7" Wire Line Bridge Plug below top of cement with 6' cement on top.  
Shoot 7" casing, pull 1 joint and displace cement thru 7" to base of surface casing. Pull 7", set bridge and 10' cement to bottom of cellar.

Very truly yours,

Conservation Division Agent